

### **QUITO PARK SCOPE OF WORK OPTION 1**

1. Remove existing playground
2. Remove existing sand down to subgrade and up to new concrete mow curd
3. Install new playground per plan
4. Install 15 leech pits per detail (parks will mark locations)
5. Install approximately 43' X 6" X 18" concrete curb (option 1 only)
6. Install PIP per plan
7. Install EFW per plan
8. Installer is responsible for installing 6' chain-link fencing around entire footprint of the project
9. Installer is responsible for diversion requirements

### **QUITO PARK SCOPE OF WORK OPTION 2**

1. Remove existing playground
2. Remove existing sand down to subgrade
3. Install new playground per plan
4. Install 15 leech pits per detail (parks will mark locations)
5. Install PIP per plan
6. Install EFW per plan
7. Installer is responsible for installing 6' chain-link fencing around entire footprint of the project
8. Installer is responsible for diversion requirements